

Superintending Archaeologist,
Archaeological Survey of India
Agrā Circle, Agrā

Price of Tender Form : OFFICE OF THE SUPERINTENDING ARCHAEOLOGIST
Rs. 500/- ARCHAEOLOGICAL SURVEY OF INDIA
AGRA CIRCLE, 22 MALL ROAD, AGRA
MEMORANDUM
TENDER FOR EXECUTION OF WORK

NAME OF WORK:- CONSTRUCTION OF BOUNDARY WALL AT SASSANI MOUND ALIGARH.

Tender are hereby invited on behalf of the President of India for execution of work described in the present memorandum according to the specifications within the time scheduled and at the rates quoted therein subject to the terms and conditions of the contract as specified in Form 6 and 8/9 C.P.W.D.
i) Earnest Money Rs. 56,048.00
ii) Security Deposit Rs. 10% at the time of Agreement of lowest tenderer
iii) Percentage to be deducted from bill Rs.

Last date to sale the tender 22/01/2015 AT 16.00 Hrs.
Date to open the tender 23/01/2015 At 15.15

Sl. No	Description Specifications of works to be executed	Total quantities each to be executed	Places where to be executed	Quantities to be executed at each place	Dates by which to be executed at all places.	Rates at which articles are to be executed inclusive of every demand.	Per unit	Total Cost Remarks of each article/item inclusive of every demand.
1	Removal of Vegetation including supply of T&P etc. required for completion of work.	880.00					Sqm	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth/lead upto 50m and lift upto 1.5m. disposed earth to be levelled and neatly dressed.	198.00					Cum	
3	Providing and laying in position cement concrete of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) in foundation	33.00					Cum	
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12graded stone aggregate 20 mm nominal size) upto plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)	132.00	Sassani Mound Aligarh	Full	180 days		Cum	
5	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand)	257.40					Cum	
6	Raised and cut pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand)	1144.00					Sqm	
7	Providing and laying in position cement concrete of 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level, including finishing complete.	24.75					Cum	
Total								

NOTE: TENDER WILL BE REJECTED IF: 1. OVERCUTTING/OVERWRITING FOUND 2. ITEM WISE TENDER RATE & ITS GRAND TOTAL (INCASE OF COMPLETE WORK) NOT MENTIONED. 3. WITNESS CONTRACTOR SIGNATURE ARE NOT FOUND. 4. OTHER DISCREPANCIES ARE FOUND.

Signature of Contractor

Should this tender be accepted, I/we hereby agree to abide by and fulfill all the terms and provisions of the said condition annexed hereto (C.P.W.D. 7/8) so far as applicable, and or in default thereof to forfeit and pay to the President of India of his successor in office the sum of earnest money mentioned in the said condition. A sum of Rs..... is forwarded herewith in fix deposit as earnest money. If I/we fail to supply the materials commence the work a specified in the above memorandum or if I/we fail to deposit the as mount of security deposit specified against (ii) (a) in the above memorandum in accordance with the clause I of the said condition of contract I/we agree that the said President or his successors in office shall, without prejudice to any other right or remedy, shall be retained by him towards such security deposit. I/we further agree that the said President or his successors in office shall also be at liberty to cancel the acceptance of the tender if I/we fail to deposit security amount as aforesaid.

Signature & Full Address

**With Registration Number of the Contractor
Seal of the Firm**


Signature of witness to Signature of tender
.....Address.....

Dated the:-

**Signature of the office by
Whom the tender is accepted
(Seal of the Office)**

The above tender is hereby accepted by me on behalf of the President of India.

Dated the:-



TENDER NOTICE

प्रल्कीर्षि गणवृणु


भारत के राष्ट्रपति की और से अधीक्षण पुरातत्त्वविद्, भारतीय पुरातत्त्व सर्वेक्षण, आगरा मण्डल, आगरा के द्वारा मुहरबन्द निविदायें निम्नलिखित कार्य हेतु भारतीय पुरातत्त्व सर्वेक्षण, में पंजीकृत टेकदारों, के लिये निविदा आमंत्रित की जाती है।

कार्यालय अधीक्षण पुरातत्त्वविद्, भारतीय पुरातत्त्व सर्वेक्षण, 22, माल रोड, आगरा मण्डल, आगरा प्रत्येक कार्यालय अवधि में आयकर एवं स्थायी लेखा सख्या दिखाकर निविदा प्रपत्र रुपये 500.00 प्रत्येक निविदा प्रपत्र (बिना वापसी) की क्य की जा सकती है। निविदा तिथि 22/01/2015(16.00 बजे तक) एवं निविदा प्रपत्र खोलने की तिथि 23/01/2015 (15.15 बजे)

Name of Work	Description of Execution of Work	Total Quantity to be Executed	Estimated Cost	Earnest Money	Period of Executed	Cost of Tender Form
1. Construction of Boundary wall at Sassani Mound Aligarh	Removal of Vegetation including supply of T&P etc. required for completion of work.	880.00				
2.	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30cm in depth, 1.5 m in widths well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.	198.00				
3.	Providing and laying in position cement concrete of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) in foundation	33.00				
4.	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12graded stone aggregate 20 mm nominal size) upto plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)	132.00	22,41,918.00	56,048.00 (Only FDR)	180 Days	500.00
5.	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand)	257.40				
6.	Raised and cut pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand)	1144.00				
7.	Providing and laying in position cement concrete of 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level : including finishing complete.	24.75				

Endt. No. 3/MT/H/45/2014-2015/W

Copy to - C.C. Section, Agra Circle, Agra for information and uploading the same on the official web site of Agra Circle i.e. www.asiagracircle.in immediately.



एक कदम स्वच्छता की ओर

स्वच्छ भारत, स्वच्छ आगरा, स्वच्छता हमारी जिम्मेदारी, जन-जन की भागीदारी

Superintending Archaeologist

(Signature)