

PRICE OF TENDER FORM : OFFICE OF THE SUPERINTENDING ARCHAEOLOGIST Last date to sale the tender 22/10/2015 AT 16.00 Hrs.
 RS. 500/- ARCHAEOLOGICAL SURVEY OF INDIA Date to open the tender 23/10/2015 At 15.15 Hrs.

AGRA CIRCLE, 22 MALL ROAD, AGRA
 MEMORANDUM

TENDER FOR EXECUTION OF WORK
 NAME OF WORK:- REPAIRS TO BOUNDARY WALL OF KANKALI TEELA MATHURA.

Tender are hereby invited on behalf of the President of India for execution of work described in the present memorandum according to the specifications within the time scheduled and at the rates quoted therein subject to the terms and conditions of the contract as specified in Form 6 and 8/9 C.F.W.D.

i) Earnest Money Rs. 35,179.00
 ii) Security Deposit Rs 10% at the time of Agreement of lowest tenderer
 iii) Payable immediately on the acceptance of tender (including earnest money if deposited in F. D. R./Call Deposit with tender) Rs.
 (iii) Percentage to be deducted from bill Rs.

[Signature]
 Superintendent Archaeologist,
 Archaeological Survey of India
 Agra Circle, AGRA

Sl. No	Description Specifications of works to be executed	Total quantities each to be executed	Places where to be executed	Quantities to be executed at each place	Dates by which to be executed at all places.	Rates at which articles are to be executed inclusive of every demand.	Per unit	Total Cost of each article/item inclusive of every demand.	
1.	Details is Enclosed		Kankali Teela, Mathura	Full	180 days				
Total									

NOTE: TENDER WILL BE REJECTED IF: 1. OVERCUTTING/OVERWRITING FOUND 2. ITEM WISE TENDER RATE & ITS GRAND TOTAL (INCASE OF COMPLETE WORK) NOT MENTIONED. 3. WITNESS CONTRACTOR SIGNATURE ARE NOT FOUND. 4. OTHER DISCREPANCIES ARE FOUND.

Signature of Contractor

Should this tender be accepted, I/we hereby agree to abide by and fulfill all the terms and provisions of the said condition annexed hereto (C.P.W.D. 7/8) so far as applicable, and or in default thereof to forfeit and pay to the President of India of his successor in office the sum of earnest money mentioned in the said condition. A sum of Rs..... is forwarded herewith in fix deposit as earnest money. If I/we fail to supply the materials commence the work a specified in the above memorandum or if I/we fail to deposit the as mount of security deposit specified against (ii) (a) in the above memorandum in accordance with the clause I of the said condition of contract I/we agree that the said President or his successors in office shall, without prejudice to any other right or remedy, shall be retained by him towards such security deposit. I/we further agree that the said President or his successors in office shall also be at liberty to cancel the acceptance of the tender if I/we fail to deposit security amount as aforesaid.

Signature & Full Address

With Registration Number of the Contractor
Seal of the Firm

Signature of witness to Signature of tender
.....Address.....

Dated the:-

Signature of the office by
Whom the tender is accepted
(Seal of the Office)

The above tender is hereby accepted by me on behalf of the President of India.

Dated the:-

NAME OF WORK- Repairs to Boundary wall of Kankali Teela Mathura

Sl. No	Description of work	Total Quantity to be Executed	Rate	Amount
1.	Dismantling and taking out old M.S. Grill Railing from brick masonry wall very carefully, and stacking of serviceable material including removal of malwa at a suitable place as per direction of engineer in charge a distance of 300mt. Away from site.	34.50	sqm.	
2.	Dismantling of old brick masonry from superstructure and plinth including stacking serviceable brick and removal of debris (malwa) away from site as directed by the Engineer-In-charge within a distance of 300mt.	2.65	cum.	
3.	Dismantling old plaster raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	375.94	sqm.	
4.	Earth work in Excavation over area (exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50m & lift upto 1.5m disposed earth to be leveled and neatly dressed.	56.41	cum.	
5.	P/L in position cement concrete of 1:4:8 ratio (1cement, 4 C. sand, &8 Stone aggraded) aggregate 40mm nominal size excluding the cost of centering & shutting	14.10	cum.	
6.	Brick work in cement mortar 1:6 in foundation using first class bricks of class designation 75 including curing etc. complete.	37.61	cum.	
7.	Brick work in cement mortar 1:6 in super structure using first class bricks of class designation 75 including curing etc. complete.	44.70	cum.	
8.	P/L D.P.C. 40mm thick with cement concrete 1:2:4 (1 Cement : 2 C. Sand : 4 Stone aggregated 20mm nominal size) on plinth level.	62.90	sqm.	
9.	15mm thick cement plaster on brick wall with cement mortar in the ratio 1:4 (1cement :4 C. Sand) complete..	779.19	sqm.	
10.	P/L in position cement concrete of 1:2:4 (1 cement, 2 C. sand, & 4 graded stone grit) aggregate 20mm nominal size excluding the cost of centering & shuttering including finishing complete.	2.88	cum.	
11.	Providing & Fixing M.S. iron grill with cement concrete block size 20x.30x0.30 cmt. In the ratio 1:2:4 (1Cement:2Coarse sand 4 Stone aggregate 20mm nominal size) complete	2600.00	Kg.	
12.	Fixing old M.S. iron grill with cement concrete cement concrete block size 20x 30x0.30 cmt. In the ratio 1:2:4 (1Cement:2Coarse sand 4 Stone aggregate 20mm nominal size) complete after minor repairing of M.S. Grill etc	118.50	sqm.	
13.	Finishing walls with water proofing cement paint Snowcem new or old work with two or more coat incl. supply of all materials labour T.& P. etc.	1251.42	sqm.	
14.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade two or more coat including priming coat of approved brand primer on new surface of M.S. iron.	1557.84	sqm.	
15.	Supply & fixing 4.50x1.00m. Cattel gaurd with 0.75mm dia G.I. pipe & R.S. 150x.75mm including supply of T&P & material etc. as per required for completion of work. as per Drawing enclosed.	1.00	Job	
16.	Re fixing of old M.s. gate after repairing including required material etc. 3.30x1.60m in 1:2:4 cement concrete block size 0.50x0.50x0.60 mt.	1.00	Job	
17.	Repairing & fixing old Revolving gate in 1:2:4 cement concrete block size 0.50x0.50x0.60 mt. complete.	1.00	Job	
18.	Fixing old M.S. iron grill with cement concrete cement concrete block size 20x.30x0.30 cmt. In the ratio 1:2:4 (1Cement:2Coarse sand 4 Stone aggregate 20mm nominal size) complete after minor repairing of M.S. Grill etc	1.00	Job	
		Total		

Signature of Contractor



TENDER NOTICE

प्रतिकांति मणवावृणु

भारत के सार्वभूमि की ओर से अधीक्षण पुरातत्वविद्, भारतीय पुरातत्व सर्वेक्षण, आगरा मण्डल, आगरा के द्वारा मुहरबन्द निविदाये निम्नलिखित कार्य हेतु भारतीय पुरातत्व सर्वेक्षण, में पंजीकृत ठेकेदारों, के लिये निविदा आमंत्रित की जाती है।

कार्यालय अधीक्षण पुरातत्वविद्, भारतीय पुरातत्व सर्वेक्षण, 22, माल रोड, आगरा मण्डल, आगरा प्रत्येक कार्यालय अर्थात् में आयकर एवं स्थायी लेखा संख्या दिखाकर निविदा प्रपत्र रूपये 500,00 प्रत्येक निविदा प्रपत्र (बिना वापसी) की कय की जा सकती है। निविदा तिथि 22/01/2015 (16.00 बजे तक) एवं निविदा प्रपत्र खोलने की तिथि 23/01/2015 (15.15 बजे)


Name of Work	Description of Execution of Work	Total Quantity to be Executed	Estimated Cost	Earnest Money	Period of Executed	Cost of Tender Form
Repairs to Boundary wall of Kankali Teela Mathura	1. Dismantling and taking out old M.S. Grill Railing from brick masonry wall very carefully, and stacking of serviceable material including removal of malwa at a suitable place as per direction of engineer in charge a distance of 300mt. Away from site.	34.50				
	2. Dismantling of old brick masonry from superstructure and plinth including stacking serviceable brick and removal of debris (malwa) away from site as directed by the Engineer-In-charge within a distance of 300mt.	2.65				
	3. Dismantling old plaster raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	375.94				
	4. Earth work in Excavation over area (exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50m & lift upto 1.5m disposed earth to be leveled and neatly dressed.	56.41				
	5. P/L in position cement concrete of 1:4:8 ratio (1cement, 4 C. sand, & 8 Stone aggregated) aggregate 40mm nominal size excluding the cost of centering & shutting	14.10	14,07,164.00	35,179.00 (Only FDR)	180 Days	500.00
	6. Brick work in cement mortar 1:6 in foundation using first class bricks of class designation 75 including curing etc. complete.	37.61				
	7. Brick work in cement mortar 1:6 in super structure using first class bricks of class designation 75 including curing etc. complete.	44.70				
	8. P/L D.P.C. 40mm thick with cement concrete 1:2:4 (1 Cement : 2 C. Sand : 4 Stone aggregated 20mm nominal size) on plinth level.	62.90				
	9. 15mm thick cement plaster on brick wall with cement mortar in the ratio 1:4 (1cement :4 C. Sand) complete..	779.19				
	10. P/L in position cement concrete of 1:2:4 (1 cement, 2 C. sand, & 4 graded stone gri) aggregate 20mm nominal size excluding the cost of centering & shuttering including finishing complete.	2.88				
	11. Providing & Fixing M.S. iron grill with cement concrete block size 20x 30x0.30 cmt. In the ratio 1:2:4 (1Cement:2Coarse sand 4 Stone aggregate 20mm nominal size) complete	2600.00				

12	Fixing old M.S. iron grill with cement concrete cement block size 20x30x0.30 cmt. In the ratio 1:2:4 (1Cement:2Coarse sand 4 Stone aggregate 20mm nominal size) complete after minor repairing of M.S. Grill etc	118.50	sqm.			
13	Finishing walls with water proofing cement paint Snowcem new or old work with two or more coat incl. supply of all materials labour T. & P. etc.	1251.42	sqm.			
14	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade two or more coat including priming coat of approved brand primer on new surface of M.S. Iron.	1557.84	sqm.			
15	Supply & fixing 4.50x1.00m. Cattel gaurd with 0.75mm dia G.I. pipe & R.S. 150x75mm including supply of T&P & material etc. as per required for completion of work. as per Drawing enclosed.	1.00	Job			
16	Re fixing of old M.s. gate after repairing including required material etc. 3.30x1.60m in 1:2:4 cement concrete block size 0.50x0.50x0.60 mt.	1.00	Job			
17	Repairing & fixing old Revolving gate in 1:2:4 cement concrete block size 0.50x0.50x0.60 mt. complete.	1.00	Job			
18	Fixing old M.S. iron grill with cement concrete cement concrete block size 20x30x0.30 cmt. In the ratio 1:2:4 (1Cement:2Coarse sand 4 Stone aggregate 20mm nominal size) complete after minor repairing of M.S. Grill etc	1.00	Job			


Superintending Archaeologist

Endt. No. 3/MT/H/09/2014-2015W

Copy to - C.C. Section, Agra Circle, Agra for information and uploading the same on the official web site of Agra Circle i.e. www.asiagr.circle.in immediately.


रक्षक संरक्षक स्नायुकेता श्री अग्र

रक्षक संरक्षक, रक्षक अग्र, रक्षक अग्र, जन-जन की आशीर्वादी